SECTION 07 00.00

SESCO Si750 WHITE SILICONE ROOF RESTORATION SYSTEM
STRUCTURAL CONCRETE ROOFING SYSTEMS

PART 1 - GENERAL

1.1 DESCRIPTION

This section establishes requirements for the installation of **SESCO Si750** to Structural Concrete and Other Concrete surfaces.

The roof restoration system is intended to:

1. Extend the service life of concrete roofing assemblies.
2. Provide a seamless weather-resistant surface.
3. Improve solar reflectivity and reduce roof surface temperatures.
4. Prevent roof replacement when the existing roof remains structurally sound.

1.2 ROOF ELIGIBILITY

The roof coating system may be installed over:

1. Cast-In-Place Structural Concrete Roof Decks
2. Pre-Cast Structural Concrete Roof Decks- (aged more than 60 days).

The system shall not be installed over:

1. Light Weight Insulating Concrete.
2. Green Concrete less than 60 days.
3. Polished Concrete.
4. Split-Slab, topping slab conditions.

1.3 DESIGN CONSIDERATIONS

The silicone coating system is intended for roofs exhibiting normal weathering and aging. Prior to restoration, the roofing assembly shall be evaluated to verify that:

1. The substrate is dry and stable.
2. Existing membranes remain securely attached.
3. Structural components remain serviceable.
4. Positive drainage is recommended. Roof areas exhibiting chronic standing water shall be reviewed before installation.

1.4 ADHESION VERIFICATION

Representative adhesion testing shall be performed before installation of the roofing system. Testing shall verify compatibility of the existing substrate with all restoration materials. Test results should be a minimum of 2lbs per lineal inch of fabric width.

1.5 RELATED WORK

Coordinate work under this section with:

a) Sheet metal flashings
b) Roof accessories
c) Mechanical curbs

d) Roof drains
e) Equipment supports
f) Penetrations and pipe flashings

1.6 SUBMITTALS

A. **Product Data:**
Submit manufacturer's standard submittal package including specification, installation instructions, and general information for each waterproofing material.

B. **Applicator Qualifications:**
Applicator Qualifications: The applicator shall be approved by SESCO Roofing Products. The manufacturer's written verification of applicator approval is required.

C. **Substrate Conditions:**
1. Applicator to present to owner a completed inspection report verifying substrate condition and any noted defects not specifically addressed regarding the installation of the coating.
2. Surface shall be free from loose dirt, stone, debris, moisture, and shall be in stable condition. Any work on the area to receive this application shall be completed prior to the installation of the coating.
3. Applicator shall complete a substrate inspection prior to the start of the installation of the coating. The architect/owner and applicator shall accept the substrate. Start of the work constitutes acceptance.

1.7 QUALIFICATIONS

A. Products shall be supplied by a single manufacturer and designed to function as a complete roof restoration system. Manufacturer shall have been in business for (20) years.

B. Applicators shall have a minimum of five (5) years' experience and 1 million square feet in the application of waterproofing materials of the type specified. The Applicator shall possess a current Letter of Good Standing from the specified waterproofing manufacturer.

C. **Mandatory Pre-Bid Conference:**
Ten (10) working days prior to the bid opening there is to be a mandatory Pre-Bid Conference. Those not attending the Pre-Bid Conference will not be allowed to bid the project. All products considered equal to the specified product or any changes in the scope of work, installation, or specifications must be presented at the Pre-Bid Conference. If a change in the specifications is accepted, it will be considered as an alternate and will be presented as a bid addendum issued five (5) working days prior to the bid opening. No other changes to the specification or bid documents will be accepted.

D. Materials other than those specified shall be submitted to the architect/owner for approval no later than ten (10) days prior to the bid date. In requesting prior approval, it shall be necessary to submit: 1. A letter of certification, signed by an officer of the manufacturer, stating that the alternate material is equal to or better than the specified product. 2. Independent laboratory test data giving physical property values in comparison to the specified material.

E. **Pre-Installation Conference:** Just prior to the commencement of the installation, meet at the jobsite with a representative of the coating manufacturer, applicator, general contractor, architect, and other parties affected by this section. Review the methods and procedures, substrate conditions, scheduling, and safety.

1.8 DELIVERY, STORAGE, AND HANDLING

1. Deliver materials in original unopened containers bearing manufacturer identification.
2. Store materials in accordance with published manufacturer requirements.
3. Protect products from freezing temperatures, excessive heat, moisture, and contamination.

1.9 WARRANTY

A. Manufacturer warrants that the material supplied will meet or exceed physical properties as published. The Applicator guarantees that workmanship will be free of defects in coating application. Since performance previously applied coatings is beyond the control of Manufacturer and Applicator, requests for additional warranty coverage shall be subject to prior approval by Manufacturer.

B. A TEN (10) YEAR LABOR AND MATERIAL WARRANTY MUST BE OBTAINED THROUGH THE MANUFACTURER

PART 2 - PRODUCTS

2.1 MANUFACTURERS

ACCEPTABLE MANUFACTURERS- SESCO Roofing Products, SESCOROOF.COM

2.2 MATERIALS

A. **BLEED BLOCKING PRIMER**
SESCO ROOF Pr345 CONCRETE PRIMER

B. **FLASHING**
SESCO ROOF Si790 MASTIC

C. **POLYESTER MESH**
SESCO POLYESTER REINFORCING MESH

D. **SILICONE ROOF MEMBRANE**
SESCO ROOF Si750 ROOF MEMBRANE

Minimum Physical Properties

Physical Property	Typical Value	Test Method
Solids by Weight	98%	ASTM D 1644
Solids by Volume	96%	ASTM D 2697
Tensile Strength	220 PSI	ASTM D 2370
Elongation	275%	ASTM D 2370
SRI	110	ASTM E1980
VOC	<45 g/l	EPA Method 24
Permeance	6.0 Perms	ASTM E 96

PART 3 - EXECUTION

3.1 EXAMINATION

B. Inspect surfaces that will receive the coating system to make sure they are clean, smooth, sound, properly prepared, and free of moisture, dirt, debris, or other contamination.
C. Verify that all roof penetrations, mechanical equipment, cants, edge metal, and other on-roof items are in place and secure.
D. Verify that all critical areas around the immediate vicinity of the spray area are suitably protected.
E. Verify that all roof drains are clean and in working order by means of a water test.

F. Verify that all air conditioning and air intake vents are suitably protected or closed.

3.2 SURFACE PREPARATION

Cleaning

A. Thoroughly clean the substrate by pressure washing at a minimum operating pressure of **3,000 psi**. The surface must be free of dirt, dust, loose or failing coatings, and all contaminants, including oils, oil-based roof cement, solvents, grease, animal fats, and similar residues.
C. Cleaning methods shall not damage the existing roofing substrate..
E. Areas containing mildew, algae, or fungus shall be treated and cleaned prior to coating.

3.3 Installation

The roofing system shall be installed in accordance with the manufacturer's published requirements and with support from the manufacturer's technical team. Contractors are encouraged to consult Technical Services for guidance on application procedures, substrate conditions, and project-specific recommendations.

B. **Primer Application**
   1. For concrete roofs less than 1 year old prime with **Pr345 Primer** at a coverage rate of **150 square feet per gallon**. Porous or rough substrates may require additional material to obtain full coverage.

C. **Roof Coating Preparation**

All Seams, Penetrations and Wall details

1. **Penetrations:** Apply **Si790 Mastic** at a rate of 60 dry mils min. Application shall encapsulate the area around the penetration. Application shall extend a minimum of 4” on to the existing roof membrane taper the edges smoothly onto the surrounding roof surface.
2. **Parapet Walls:** Apply **Si790 Mastic** to all seams and flashings on parapet walls at a rate of 30 dry mils. Application shall be a minimum of 4” wide over the seam. taper the edges smoothly onto the surrounding roof surface.
4. **Flashings:** Apply a layer of **Si790 Mastic** 4’ wide at flashing points 60 dry mils min. Application should be made to insure water tightness of the flashing detail.

Crack and Split Treatment

1. **Minor Cracks and Splits (Less Than 1/4 Inch)**
   a. Fill and seal the defect with **Si790 Mastic**, ensuring complete coverage of the opening.
   b. Extend the repair material at least **4 inches beyond the damaged area** and taper the edges smoothly onto the surrounding roof surface.
2. **Major Cracks and Splits (Greater Than 1/4 Inch)**
   a. Apply **Si790 Mastic** to fully seal and fill the damaged area.
   b. Continue the application a minimum of **4 inches beyond the crack or split** and taper the edges smoothly onto the surrounding roof surface.
   c. After the repair area has been filled and brought level with the existing roof surface, install a strip of **polyester reinforcement fabric** of sufficient width to extend at least **2 inches past each side** of the defect.
   d. Apply an additional layer of **Si790 Mastic or Si750 High Solids Silicone** to completely cover and saturate the reinforcement.
   a. Apply an additional layer of **Si750 High Solids Silicone** to completely cover and saturate reinforcement

D. **SILICONE MEMBRANE APPLICATION**
   a. Apply **Si750 White Silicone Roof Coating** uniformly in multiple coats over prepared roof surfaces.

b. Coverage rate shall be sufficient to achieve a minimum finished dry film thickness as specified.

LABOR AND MATERIAL WARRANTY TERM	MINIMUM APPLICATION RATE
10 Years	2 Gallons/sq. (28 wmt/24dft)
15 Years	2.5 Gallons/sq. (40 wmt/35dft)
20 Years	3 Gallons/sq. (45 wmt/40 dft)

NOTE: For rough surfaces, more material may be needed to achieve the required mil thicknesses.

Additional coating shall be applied at transitions, flashings, repairs, granulated surfaces, and other irregular areas as necessary to achieve the specified minimum as specified.

Application shall not occur during precipitation, when moisture is present on the substrate, or when weather conditions may adversely affect curing.

WALKPAD (OPTIONAL)

Where specified, install walkpads as manufactured by SESCO Roofing Products

GRANULE SURFACE (OPTIONAL)

Where specified, apply an additional coat of **Si750 High Solids Silicone** at 10 mils and immediately broadcast **SESCO Roofing Granules manufactured by SESCO Roofing Products** at a rate of 30lbs/sq at a uniform rate sufficient to achieve full embedment and consistent appearance. Granules shall be distributed evenly while the coating remains wet.

QUALITY CONTROL INSPECTION

Verify by field measurement that the completed roofing system achieves a minimum dry film thickness as specified, any variations shall be corrected by the applicator.

MINIMUM DRY FILM THICKNESS (DFT) REQUIREMENT: SESCO ROOFING PRODUCTS recommends adding a 10 % variance factor to meet the minimum Dry Film Thickness (DFT) mil requirement to qualify as a warrantable application. It is the Applicator's responsibility to calculate the amount of coating needed to obtain the minimum Dry Film Thickness (DFT) mil thickness.

END OF SECTION 07 00 00.